Published by :
https://www.ijert.org/
An International Peer-Reviewed Journal

International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 14, Issue 12, UCBO - 2026

A Study on Operations Management and Resource Planning in Construction Projects at Shri Krupasindhu Infra Projects

Aditya Salunke
Student, MBA- Operations and Supply Chain Management,
School of Business,
Indira University,
Pune, India 41103

Dr. Manisha Maddel
Associate Professor & Guide, School of Business,
Indira University,
Pune, India-411033
manisha.maddel@indiraisbs.edu.in
ORCID: 0009-0008-1720-2959

Dr. Hetal Bhinde
Associate Dean Ph.D. Programs,
School of Business,
Indira University,
Pune, India-411033
hetalb19@gmail.com
ORCID: https://orcid.org/0000-0002-6435-5113

Abstract **- The construction and infrastructure sector operates in a dynamic, project-based environment where execution continuity hinges on the synchronized availability of materials, machinery, and skilled labor. Grounded in established operations management, lean construction, and supply chain theories emphasizing constraint removal, rolling-horizon planning, and contractual risk-sharing, this study examines site-level execution at Shri Krupasindhu Infra Projects, an emerging contracting firm based in Igatpuri, Maharashtra. The primary objectives were to evaluate day-to-day operations across concurrent client sites, analyze procurement practices for critical materials like plywood, steel, and channels, assess resource-planning and shortage-mitigation mechanisms, and formulate actionable recommendations to enhance site readiness. Methodologically, the study employed an applied, descriptive single-case study design conducted over an eight-week timeframe (30 June to 31 August 2026), gathering qualitative empirical data through daily on-site observations, structured mentor discussions, and fortnightly learning logs across active highway, drainage, and retaining-wall contracts for key clients including Ashoka Buildcon, Unico Infracon, and the Lodha Group. The findings reveal that the organization maintains operational stability through two strategic pillars: an active fifteen-day rolling forecast for materials and manpower, and contractual risk-sharing clauses authorizing clients to provide emergency resources during unforeseen shortages. Additionally, strategic buyer-supplier relationships secure vital inputs, such as formwork plywood, below prevailing market rates. However, day-to-day site tracking, inventory control, and vendor evaluations rely heavily on centralized, undocumented coordination. The study concludes that while this lean, relationship-driven framework effectively prevented project downtime, it poses scalability bottlenecks as order volumes expand. To ensure sustainable growth, the study recommends institutionalizing low-cost digital rolling requirement registers, adopting monthly vendor performance scorecards, executing 48-hour work-front readiness checks, and standardizing emergency resource clauses in future client work orders. These practical interventions provide a robust operational blueprint for scaling emerging infrastructure enterprises.**

Index Terms **- Operations Management, Resource Planning, Construction Supply Chain, Vendor Coordination, Risk Mitigation**

I. INTRODUCTION

The construction and infrastructure sector serves as a fundamental driver of economic expansion, generating substantial employment and spurring demand across critical allied industries such as steel, cement, and logistics. Unlike traditional, repetitive manufacturing environments characterised by static production lines, construction operations are inherently project-based, geographically fragmented, and susceptible to severe environmental and market disruptions. Every project demands bespoke execution schedules, dynamic resource allocations, and seamless multi-stakeholder coordination. Within this high-stakes environment, operational efficiency hinges heavily on the synchronized and timely availability of essential materials, machinery, and skilled labor. Any failure in site-level coordination or procurement foresight inevitably triggers cost overruns, idle manpower, and compromised project timelines.

To examine these ground-level operational realities, this research investigates the operational frameworks and resource-planning mechanisms of Shri Krupasindhu Infra Projects, an emerging contracting firm based in Igatpuri, Nashik. Undertaken as part of an On-the-Job Training (OJT) engagement, the study evaluates the company's day-to-day execution across concurrent road, highway, drainage, and retaining-wall contracts for established developers, including Ashoka Buildcon, Unico Infracon, and the Lodha Group. Field observations reveal that the enterprise maintains operational stability through a disciplined 15-day rolling forecast for critical inputs—such as shuttering plywood, structural steel, channels, cement, ready-mix concrete, and binding wire—complemented by contractual risk-mitigation clauses where clients step in during critical supply shocks.

Ultimately, this study bridges theoretical principles of operations management and supply chain logistics with empirical, site-level practices. It critically examines material procurement channels, storage protocols, and manpower scheduling, highlighting how strategic vendor relationships unlock cost advantages beneath prevailing market rates. By identifying existing operational constraints in manual tracking and inter-site coordination, this research delivers practical recommendations to institutionalize material tracking, formalize supplier performance metrics, and enhance resource readiness, providing a scalable operational blueprint for growing infrastructure enterprises.

(This work is licensed under a Creative Commons Attribution 4.0 International License.)

International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 14, Issue 12, UCBO - 2026

II. THEORETICAL BACKGROUND AND LITERATURE REVIEW

Construction operations management focuses on converting technical designs and raw inputs into completed physical assets through coordinated sequencing, productivity monitoring, and schedule control across dynamic site environments [1]. Because construction activities occur along an evolving physical flow, operational continuity relies strictly on proactive constraint removal and resource readiness [2]. Within this setting, construction supply chain management connects procurement, storage, and site execution into a synchronized pipeline [3]. At Shri Krupasindhu Infra Projects, this dynamic is reflected in strategic vendor relationships that yield cost advantages—such as securing shuttering plywood below market rates—and ensure reliable delivery.

Balancing on-site stock availability against holding costs requires structured resource planning [4]. The firm operationalizes this balance through a 15-day rolling-horizon forecast, aligning material arrivals and labor allocations with near-term execution needs to mitigate stock-outs without creating on-site congestion. This strategy reflects lean construction principles, which seek to eliminate wastes of waiting, excessive staging, and idle capacity [5].

Complementing these planning mechanisms, contract management theory highlights formal risk-sharing provisions to absorb unexpected external shocks [6]. The enterprise leverages work-order clauses that permit principal clients to inject emergency material or manpower buffers during critical shortages, shielding the sub-contractor from unilateral downside risk. Combined with Total Quality Management principles emphasizing process compliance and defect prevention [7], this integrated theoretical framework underpins how the enterprise synchronizes procurement, risk allocation, and site-level execution.

III. MATERIALS AND METHODS

A. Objectives of the Study

The primary aim of this investigation is to evaluate site-level operations and resource management at Shri Krupasindhu Infra Projects. The specific objectives guiding this study are:

O1: To understand the day-to-day construction and infrastructure project operations of Shri Krupasindhu Infra Projects and how work is coordinated across client sites.

O2: To study the company's material procurement and vendor-coordination practices, with specific reference to key materials such as plywood, steel, channels, and binding wire.

O3: To examine the company's resource-planning practices for materials, manpower, and equipment, and the mechanisms used to manage shortage risk.

O4: To identify practical recommendations for strengthening material tracking, vendor management, and resource-readiness at the site level.

B. Research Design and Data Collection

This study employs an applied, descriptive case study design conducted over an eight-week timeframe from 30 June 2026 to 31 August 2026. Primary empirical data was gathered through daily on-site observations of drainage, highway, and retaining-wall works, structured discussions with company mentor Mr. Rushikesh Devale and field supervisors, and detailed field notes maintained across four distinct fortnightly monitoring cycles. The observation frame tracked workflows, resource staging, and procurement interactions for critical materials—specifically plywood, steel, channels, and binding wire—across active client sites including Ashoka Buildcon, Unico Infracon, and the Lodha Group.

C. Analytical Approach and Scope

Data was synthesized using qualitative process-mapping across five progressive stages: site orientation, procurement analysis, resource-planning evaluation, operational bottleneck identification, and practical framework design. Findings were triangulated against contractual risk-sharing clauses, internal planning schedules, and established construction management literature. Because proprietary financial accounts remained confidential, the methodology centers on qualitative process flows, forward-planning horizons, and inter-site resource allocation rather than statistical financial modeling.

IV. DATA ANALYSIS AND DISCUSSION

A. Objective 1: Operational Coordination Across Concurrent Sites

Table I illustrates the operational dynamics of Shri Krupasindhu Infra Projects across diverse civil infrastructure portfolios. The company operates as a specialized sub-contractor, managing concurrent work fronts spanning highway developments, urban drainage systems, and developer-grade retaining walls. Operational synchronization relies heavily on centralized, informal oversight led by the company mentor, supported by on-site supervisors using direct communication channels such as phone calls and messaging applications. While this direct leadership model maintains site agility and ensures alignment with client milestones, it places substantial cognitive and operational strain on key personnel. As the enterprise prepares to execute additional pipeline projects, managing geographically dispersed sites through informal communication channels poses operational bottlenecks, highlighting the necessity for structured operational workflows.

(This work is licensed under a Creative Commons Attribution 4.0 International License.)

International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 14, Issue 12, UCBO - 2026

TABLE I
OPERATIONAL DYNAMICS AND COORDINATION MECHANISMS ACROSS PROJECT SITES

Client / Partner	Scope of Infrastructure Work	Work-Front Coordination Mechanism	Key Operational Constraints	Site Coordination Tools
Unico Infracon	Drainage lines, road construction, civil earthworks	Mentor-led staging; sequencing excavation, shuttering, pouring	Monsoon weather disruptions; dynamic open drainage fronts	Direct supervision, phone updates, WhatsApp groups
Ashoka Buildcon	National Highway (NH) works, culvert construction, drainage	Synchronized multi-front scheduling; strict adherence to milestones	High compliance standards; tight milestones; lane-closure timing	Site supervisor check-ins, mentor field visits, site registers
Lodha Group	Retaining wall and gabion wall construction for real estate	Phased vertical stabilization; coordinated staging of stone and mesh	Confined work fronts; structural quality checks; staging limits	Coordinated shift planning, supervisor logs, mentor monitoring
Pipeline Projects	Upcoming road, drainage, and MIDC industrial infrastructure orders	Advance work-order pipeline evaluation; prospective site surveys	Multi-site resource contention across expanding dispersed fronts	Pre-mobilization requirement checklists, mentor allocation

B. Objective 2: Material Procurement and Vendor Coordination

Table II details the company's differentiated material procurement framework, categorizing construction inputs by functional priority and commercial dynamics. Sourcing strategies vary distinctly between high-value capital materials and low-value consumables. For high-value structural components like shuttering plywood, the company leverages relational capital, securing supplies below prevailing market rates from a trusted vendor. Structural steel and channels are procured against stringent technical specifications from authorized distributors using rolling demand schedules. Conversely, bulk perishables such as RMC follow just-in-time delivery models, while binding wire and daily consumables are purchased on an as-needed basis to minimize idle working capital. Although this sourcing mix achieves cost efficiencies and keeps operational sites supplied, tracking vendor lead times and material receipts remains informal, relying largely on memory rather than documented logs.

TABLE II
MATERIAL PROCUREMENT FRAMEWORK AND SOURCING PRACTICES

Material Category	Primary Application	Vendor Selection & Sourcing Criteria	Pricing & Commercial Terms	Procurement Horizon	Observed Inventory Practice
Plywood	Shuttering and formwork for concrete structures	Preferred long-standing vendor; high relationship trust	Below prevailing market rate via long-term relationship	15 days in advance based on execution schedules	Staged at central warehouse or covered site stores
Steel & Channels	Drainage rebar, highway culverts, structural framing	Authorized local distributors; compliance with client specifications	Competitive market pricing; negotiated credit windows	10 to 15 days advance ordering by structural milestones	Elevated on wooden sleepers to prevent rust and soil contact
Cement & Aggregates	Concrete works, drainage bedding, masonry walls	Certified regional suppliers; proximity to project sites	Competitive regional pricing; standard terms	Short-cycle rolling orders based on daily pour schedules	Moisture-proof covered storage; stacked off-ground
Ready-Mix Concrete	High-volume road beds and retaining wall pours	Authorized RMC batching plants; transit distance and pump capacity	Pre-agreed per-cubic-meter supply contracts	Scheduled 24–48 hours ahead of planned pour dates	Just-in-time delivery via transit mixers straight to pour fronts
Binding Wire & Misc.	Tying rebar, gabion mesh, general site consumables	Local hardware stockists; immediate shelf availability	Retail market rates; cash or short-term credit	On-demand procurement driven by immediate site consumption	Kept in small locked site stores to prevent theft and corrosion

C. Objective 3: Resource Planning and Shortage Risk Management

Table III evaluates the company's tripartite resource-planning framework spanning materials, manpower, and equipment. The operational backbone of Shri Krupasindhu Infra Projects is an active 15-day rolling planning horizon. Rather than operating reactively, site management anticipates material consumption, labor gang sizing, and machinery utilization two weeks ahead of execution. This forward planning is reinforced by a structural risk-mitigation strategy embedded in client work orders: explicit contractual clauses allowing principal developers (such as Ashoka Buildcon or Lodha Group) to supply materials or labor during unforeseen site emergencies. Coupled with flexible gang redeployment and preventative equipment scheduling, this dual-layered approach—proactive forecasting backed by contractual risk-sharing—has effectively minimized site stoppages, resulting in zero recorded operational halts during the evaluation period.

(This work is licensed under a Creative Commons Attribution 4.0 International License.)

International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 14, Issue 12, UCBO - 2026

TABLE III
RESOURCE PLANNING PRACTICES AND RISK-MITIGATION MECHANISMS

Resource Domain	Baseline Requirement Driver	Planning Technique & Horizon	Staging & Allocation Protocol	Operational Risk Factors	Formal Risk Mitigation Mechanism
Construction Materials	Structural drawings, pour schedules, work front readiness	15-day rolling forecast; updated against site execution velocity	Stored at central warehouse or delivered direct to work fronts	Supplier stock-outs, transport strikes, monsoons, price shifts	15-day buffer stock; contractual work-order emergency client supply
Manpower (Labor)	Daily labor-to-activity ratios (bar benders, masons, carpenters)	Schedule-driven forward planning; planned ~15 days ahead of stages	Pooled and shifted across active fronts based on order priority	Local labor scarcity, festival migration, absenteeism, weather	Flexible gang redeployment; contractual risk-sharing for client labor
Heavy Machinery	Earthmoving, excavation, compaction, concrete pumping	Aligned with material and labor schedules; synchronized tasking	Shared across sites or hired on project-specific sub-contracts	Mechanical breakdowns, mobilization delays, access limits	Preventive equipment checks; vendor replacement; client sharing

D. Objective 4: Actionable Frameworks for Operational Readiness

Table IV outlines practical, low-cost interventions designed to transition the company's operational workflows from informal, person-dependent practices to structured management systems. The proposed framework targets key operational vulnerabilities without burdening the firm's cost structure. Introducing a rolling 15-day material and manpower register establishes documented inventory visibility across concurrent sites. Similarly, institutionalizing vendor performance scorecards documents supplier delivery reliability and commercial terms, safeguarding margins as procurement volumes expand. A contractual work-order checklist ensures that emergency risk-sharing clauses are systematically replicated in future client contracts. Finally, a 48-hour work-front readiness protocol removes site constraints prior to major concrete pours, minimizing idle machine time and cementing a scalable operational foundation for upcoming infrastructure projects.

TABLE IV
PROPOSED INTERVENTIONS FOR OPERATIONAL STRENGTHENING

Proposed Intervention	Focus Operational Area	Implementation Methodology & Tools	Frequency & Responsible Person	Anticipated Outcome	Metric / Verification Indicator
Rolling Requirement Register (RMMR)	Material visibility and inter-site labor tracking	Standardized spreadsheet or manual log tracking stock and shortages	Updated weekly by site supervisor; reviewed by mentor	Eliminates reliance on memory; enhances inter-site visibility	Zero unrecorded stock-outs; variance in planned vs. consumed inputs
Vendor Performance Scorecard (VPS)	Procurement governance and vendor coordination	Formal matrix rating suppliers across price, timeliness, quality	Conducted monthly or per-delivery by procurement coordinator	Protects commercial margins; formalizes vendor relationships	On-time in-full (OTIF) delivery rate; supplier rejection percentages
Work-Order Risk Checklist (WORC)	Contractual risk mitigation and legal governance	Pre-execution compliance checklist ensuring emergency clauses	Applied prior to finalizing terms for every new client contract	Standardizes risk-sharing provisions across new partnerships	Percentage of contracts containing emergency client-supply clauses
Work-Front Readiness Review (WFRR)	Site preparation and constraint removal	48-hour pre-pour inspection verifying drawings, permits, resources	Executed 48 hours before major milestones by site team	Prevents idle labor and equipment costs; eliminates rework	On-time start rate for scheduled concrete pours and structural tasks

V. FINDINGS OF THE STUDY

The study reveals that Shri Krupasindhu Infra Projects maintains operational continuity across concurrent civil, drainage, and highway projects through a dual strategy of proactive planning and institutionalized risk-sharing. Operationally, the firm successfully coordinates multi-site execution for major clients—such as Ashoka Buildcon, Unico Infracon, and the Lodha Group—relying heavily on centralized oversight by the company mentor and direct field supervision via digital messaging. In procurement, the company balances cost and availability by segmenting materials: long-term relational contracting secures strategic inputs like shuttering plywood at below-market rates, structural steel and channels are ordered against stringent technical milestones, and standard consumables are sourced flexibly as needed. A central finding is the firm's disciplined fifteen-day rolling planning horizon for materials, manpower, and machinery, which systematically transforms volatile site requirements into manageable execution cycles. This advance forecasting is bolstered by contractual risk-sharing clauses in client work orders that authorize developer partners to supply emergency materials or labor during unforeseen bottlenecks, resulting in zero recorded work stoppages during the training period. However, the investigation identified that operational tracking, inventory audits, and supplier evaluations currently depend on memory and informal, person-dependent communication rather than standardized registers. As the enterprise scales into industrial and larger public infrastructure works, transitioning to formal rolling requirement registers, vendor performance scorecards, and standardized work-front readiness checks will be critical to institutionalize this operational resilience and sustain execution efficiency.

VI. SUGGESTIONS AND PRACTICAL RECOMMENDATIONS

To institutionalize operational efficiency across clients, management, site supervisors, and suppliers, Shri Krupasindhu Infra Projects should implement four low-cost interventions:

1) **Adopt a Rolling 15-Day Material and Manpower Register:** Updated weekly on cloud spreadsheets, giving management and site engineers shared visibility over stock levels, scheduled labor, and site readiness.

(This work is licensed under a Creative Commons Attribution 4.0 International License.)

International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 14, Issue 12, UCBO - 2026

2) **Implement a Monthly Vendor Performance Scorecard:** Systematically evaluate suppliers on lead-time adherence, material quality, and pricing to protect commercial margins as procurement volumes expand.
3) **Introduce a 48-Hour Work-Front Readiness Checklist:** Conducted jointly by site supervisors and client representatives before major concrete pours or structural works to prevent idle equipment and rework.
4) **Institutionalize a Pre-Contract Risk Protocol:** Ensure that mutually agreed emergency resource-sharing clauses are systematically replicated in all future client work orders, preserving the firm's frontline resilience across expanding infrastructure portfolios.

VII. IMPLICATIONS FOR STAKEHOLDERS

The study carries direct operational implications across four key project stakeholders:

- **Company Management & Supervisors:** Transitioning from informal memory-based tracking to documented 15-day rolling registers reduces person-dependent operational risk, streamlines multi-site supervision, and prevents idle machine and labor costs.
- **Principal Clients (Developers/EPCs):** Formalizing 48-hour work-front readiness checks and retaining contractual risk-sharing clauses ensures predictability, minimizes milestone slippages, and guarantees structural quality compliance across active sites.
- **Vendors & Material Suppliers:** Implementing objective performance scorecards establishes transparent delivery metrics, offers predictable order pipelines based on 15-day forward visibility, and fosters mutually beneficial pricing structures.
- **Site Labor & Equipment Operators:** Advance scheduling of work fronts prevents sudden wage loss or standby idle hours caused by material shortages, creating safer, well-organized working conditions and boosting overall site productivity.

VIII. FUTURE SCOPE OF THE STUDY

Future research can build upon this qualitative study by incorporating multi-quarter quantitative datasets to statistically measure procurement lead times, inventory holding costs, and material consumption variances once financial disclosures permit. Subsequent studies could also evaluate the financial viability and return on investment of deploying cloud-based mobile Enterprise Resource Planning (ERP) or digital building information modeling (BIM) tools within small-to-midsize construction firms, comparing them against traditional spreadsheet-based tracking. Additionally, expanding the analytical framework into a multi-firm comparative study across the Nashik and Western Maharashtra infrastructure corridors would help benchmark vendor negotiation dynamics and labor productivity metrics across diverse contract models, such as Item Rate, EPC, and Hybrid Annuity Mode (HAM). Finally, longitudinal research could assess the operational scalability of client risk-sharing mechanisms as the enterprise ventures into larger public bridges and MIDC industrial development projects.

IX. CONCLUSION

This study concludes that Shri Krupasindhu Infra Projects has successfully established an agile, effective operational model tailored to the dynamic demands of the infrastructure and construction sector. Despite operating in an environment vulnerable to supply chain volatility and severe weather disruptions, the company ensures execution continuity through two foundational pillars: a disciplined fifteen-day rolling resource-planning horizon and contractual risk-sharing provisions with principal clients. These mechanisms, combined with long-term relational procurement that secures critical materials like shuttering plywood at advantageous below-market rates, have effectively insulated active work fronts from critical shortages and downtime across prestigious client sites, including Ashoka Buildcon, Unico Infracon, and the Lodha Group. Nevertheless, the firm's heavy reliance on centralized, informal coordination and undocumented site communication presents a potential operational bottleneck as project volume expands. To sustain this momentum and realize the founder's long-term vision of multi-sectoral expansion, the organization must formalize its grassroots practices into structured management frameworks, including rolling inventory registers, vendor performance scorecards, and standardized work-front readiness protocols. Institutionalizing these low-cost systems will safeguard project margins, eliminate person-dependent vulnerabilities, and provide the operational scalability needed to manage larger infrastructure and industrial ventures successfully.

ACKNOWLEDGMENT

I express my sincere gratitude to the management of Shri Krupasindhu Infra Projects, especially CEO Ms. Akanksha Patankar and my company mentor Mr. Rushikesh Devale, as well as the faculty at the School of Business, Indira University, for their invaluable guidance and support throughout this study.

REFERENCES

[1] J. Heizer, B. Render, and C. Munson, *Operations Management: Sustainability and Supply Chain Management*, 13th ed. Boston, MA, USA: Pearson, 2020.
[2] L. Koskela, "Application of the new production philosophy to construction," Stanford Univ., Center for Integrated Facility Eng., Stanford, CA, USA, Tech. Rep. 72, 1992.
[3] R. Vrijhoef and L. Koskela, "The four roles of supply chain management in construction," *Eur. J. Purchasing & Supply Manage.*, vol. 6, no. 3–4, pp. 169–178, 2000.
[4] S. Chopra and P. Meindl, *Supply Chain Management: Strategy, Planning, and Operation*, 7th ed. Boston, MA, USA: Pearson, 2019.
[5] G. Ballard and G. Howell, "Lean project management," *Building Res. & Inf.*, vol. 31, no. 2, pp. 119–133, 2003.
[6] Project Management Institute, *A Guide to the Project Management Body of Knowledge (PMBOK Guide)*, 7th ed. Newtown Square, PA, USA: Project Management Institute, 2021.
[7] M. Imai, *Kaizen: The Key to Japan's Competitive Success*. New York, NY, USA: McGraw-Hill, 1986.

(This work is licensed under a Creative Commons Attribution 4.0 International License.)