International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 15 Issue 10 , October - 2026

Study of a Combipack Industrial Steam Boiler

Pathan Shahid Javed (1)
Dhatture Mohammadfaiz Irfan (2)
Sayyed Arman Imtiyaj (3)
Pandhare Soham Sanjay (4)
Department: Mechanical Engineering Programme:
Diploma in Mechanical Engineering
Subject: Power Plant Engineering

Assignment scope: a literature-based overview of boiler construction, working, performance, safety, maintenance and energy efficiency. No measured results are claimed because verified nameplate and operating data for the specific unit were not provided.

Prepared for academic study. Students should verify local boiler regulations, manufacturer instructions and site operating procedures before applying technical guidance.

Abstract - This paper presents a literature-based study of an industrial Combipack steam boiler for a Diploma in Mechanical Engineering assignment in Power Plant Engineering. It explains the purpose of a packaged boiler, the basic steam-generation process, major components, performance indicators, fuel and water considerations, operating practices, maintenance needs, and safety controls. The discussion draws on publications from the Bureau of Energy Efficiency (BEE), the U.S. Department of Energy (DOE), and the Federal Energy Management Program (FEMP). The exact model, rated pressure, steam output, fuel, and operating readings of the unit under study have not been independently verified. Therefore, the paper does not claim a measured efficiency, fuel saving, or performance test result; it provides the method and data requirements needed for a future site-based assessment.

1. INTRODUCTION

Steam is widely used in process heating, cleaning, sterilisation, humidification and power generation. A boiler transfers heat released by fuel combustion or another heat source to water, producing steam at a required pressure and temperature. Industrial boilers are commonly integrated with burners, feedwater systems, controls and safety devices to provide a compact package. The term “Combipack” may be a manufacturer or product-family designation; the exact construction and rating must be confirmed from the installed unit’s nameplate and manual rather than assumed from the name alone.

The objective of this report is to explain the working and engineering considerations of a packaged steam boiler using reliable published references. It also identifies the site data required to assess a particular boiler scientifically.

2. OBJECTIVES AND METHODOLOGY

The objectives are to: (i) describe the basic steam-generation cycle; (ii) identify common boiler components and their functions; (iii) explain efficiency and performance calculations; (iv) summarise operation, water treatment, maintenance and safety practices; and (v) prepare a checklist for collecting real operating data.

Methodology: secondary research was carried out using technical guidance published by BEE and DOE/FEMP. These references describe general boiler and steam-system principles. They are not a

(This work is licensed under a Creative Commons Attribution 4.0 International License.)

International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 15 Issue 10 , October - 2026

substitute for the specific boiler's operating manual, nameplate, statutory inspection records or measured site data.

3. OVERVIEW OF A PACKAGED STEAM BOILER

A packaged boiler is supplied as a coordinated assembly, typically including a pressure vessel, burner or combustion system, controls and selected auxiliaries. Packaged designs can reduce installation work and simplify integration, but configuration varies by manufacturer, capacity and fuel. Common industrial designs include fire-tube and water-tube boilers. In a fire-tube boiler, hot combustion gases pass through tubes surrounded by water; in a water-tube boiler, water flows through tubes heated externally by combustion gases. The actual design of the particular Combipack unit should be confirmed from its documentation.

The boiler's main duty is to deliver steam at the required pressure and flow while maintaining safe combustion, acceptable water chemistry and reliable control. The boiler is only one part of a steam system: fuel supply, feedwater treatment, condensate return, distribution piping, steam traps and end-use equipment all affect total system performance.

4. MAIN COMPONENTS AND THEIR FUNCTIONS

Boiler pressure vessel and heating surface: contain water/steam and provide the heat-transfer area. Burner and fuel train: mix fuel and air, ignite the mixture and regulate heat input. Forced-draught fan, where fitted: supplies combustion air. Feedwater pump: delivers treated water to the boiler against its operating pressure. Water-level controls: maintain water within the permitted range and initiate protective actions where required. Pressure gauge and pressure controls: indicate pressure and regulate operation. Safety valve(s): protect against excessive pressure and must not be isolated or adjusted except under authorised procedures. Blowdown connections: remove concentrated dissolved solids and sludge under controlled conditions. Flue and stack: discharge combustion products. Control panel and interlocks: monitor operating conditions and stop unsafe sequences. Depending on the model, additional equipment may include an economiser, deaerator, water softener, chemical dosing system or condensate tank.

5. WORKING PRINCIPLE

In a typical fuel-fired packaged boiler, the burner receives fuel and combustion air. The fuel burns in the furnace, releasing thermal energy. Hot gases transfer heat to the boiler heating surfaces, warming the water until steam is generated. Steam collects in the steam space or outlet system and is delivered to the process through controlled piping. Feedwater replaces the water converted to steam, while water-level controls help maintain safe inventory. Blowdown removes a portion of boiler water to control dissolved solids and suspended matter.

A simplified energy path is: fuel chemical energy □ combustion heat □ heat transfer to water □ steam energy □ process use. Some energy leaves with hot flue gas, radiation and convection from the boiler casing, blowdown, and incomplete combustion. Good operation seeks to minimise avoidable losses while respecting manufacturer limits and safety requirements.

6. BOILER PERFORMANCE AND EFFICIENCY

Boiler efficiency is the ratio of useful heat transferred to the water/steam to the energy supplied by the fuel, expressed as a percentage. Two common assessment approaches are the direct method (input-output) and the indirect method (heat-loss method). The selected method requires consistent measurement boundaries, reliable instruments and representative operating conditions.

Direct method: □ = (■s × (hs □ hfw)) / (■f × GCV) × 100, where ■s is steam mass flow rate, hs is specific enthalpy of produced steam, hfw is feedwater specific enthalpy, ■f is fuel mass flow rate and GCV is the gross calorific value of the fuel. Use consistent units. If steam quality, pressure, temperature or feedwater conditions are unknown, the result cannot be calculated reliably.

(This work is licensed under a Creative Commons Attribution 4.0 International License.)

International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 15 Issue 10 , October - 2026

Indirect method: boiler efficiency (%) = 100 − total percentage heat losses. Relevant losses may include dry flue-gas loss, water-vapour loss from fuel hydrogen and moisture, moisture in fuel, incomplete combustion, unburned fuel, blowdown and external radiation/convection. The applicable calculation procedure and assumptions should follow the chosen BEE assessment guidance.

No numerical efficiency is reported here because verified fuel consumption, steam flow, steam pressure/temperature, feedwater conditions and fuel calorific value for the specific unit were not supplied. Inventing these inputs would make the result invalid.

Important: Use a consistent set of units and a recognised test procedure; do not combine incompatible measurements.

7. FUEL, COMBUSTION AND FLUE-GAS CONSIDERATIONS

Efficient combustion requires an appropriate relationship between fuel flow and combustion air. Too little air can cause incomplete combustion and potentially hazardous carbon monoxide; excessive air increases the quantity of flue gas heated and discharged, increasing stack losses. Burner adjustment should be carried out by competent personnel using approved procedures and suitable combustion instruments. Fuel properties, burner condition, cleanliness of heating surfaces and load variation all influence performance.

Useful measurements during a planned assessment can include fuel flow, flue-gas temperature, oxygen or carbon-dioxide concentration, carbon monoxide where appropriate, ambient temperature and boiler load. Measurements should be taken at stable operating conditions and recorded with instrument details and calibration status.

8. FEEDWATER QUALITY, BLOWDOWN AND CONDENSATE RETURN

Water treatment is essential because scale, corrosion and deposits reduce heat transfer and can damage pressure parts. Treatment may include filtration, softening, reverse osmosis or other processes depending on raw-water quality and boiler requirements. Chemical treatment and blowdown must be managed according to water-analysis results, manufacturer instructions and applicable standards. The required limits depend on pressure, boiler design and the treatment programme; generic values should not be substituted for the site’s approved limits.

Blowdown controls the concentration of dissolved solids and removes sludge, but excessive blowdown wastes hot water and energy. Returning clean condensate can reduce fresh-water demand, chemical use and the energy required to heat make-up water. Condensate should be checked for contamination before return to the boiler system.

9. OPERATION, MONITORING AND SAFETY

Before start-up, authorised operators should complete the approved checklist, verify water availability and level, confirm that fuel and air systems are in the correct condition, check that required valves and instruments are serviceable, and ensure protective interlocks are available. Start-up and shutdown must follow the manufacturer’s sequence and the site’s written operating procedure. Operators should not bypass trips, defeat interlocks, force safety valves, or open pressurised equipment.

During operation, record pressure, water level, feedwater condition, fuel use, steam demand, alarms, blowdown and any abnormal sound, vibration, leakage or smoke. High pressure, low water level, flame failure, abnormal combustion and feedwater problems can create serious hazards. Boiler operation, inspection, certification and attendance requirements are jurisdiction-specific; in India, the applicable boiler legislation and state boiler authority requirements must be followed. Only suitably qualified and authorised personnel should perform regulated duties.

(This work is licensed under a Creative Commons Attribution 4.0 International License.)

International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 15 Issue 10 , October - 2026

10. MAINTENANCE AND TROUBLESHOOTING

A preventive-maintenance programme should be based on the manufacturer's instructions, statutory requirements and operating history. Typical tasks include checking burner and flame safeguards, cleaning heating surfaces when indicated, inspecting refractory and seals, checking pumps and motors, testing alarms and trips, inspecting gauges and controls, maintaining water-treatment equipment, and examining feedwater and fuel systems. Pressure parts and safety devices require inspection and testing by authorised personnel under the applicable rules.

Common symptoms and possible areas for investigation include: rising flue-gas temperature (fouling, scale or load changes); unstable water level (control, feed pump or level-sensing issue); poor combustion (burner condition, fuel quality or air adjustment); frequent blowdown (water chemistry or control practice); and steam pressure instability (load swings, control settings or inadequate capacity). These are diagnostic starting points, not instructions to alter safety-critical equipment without authorisation.

11. ENERGY CONSERVATION OPPORTUNITIES

Potential improvement measures include regular combustion tuning, cleaning heat-transfer surfaces, repairing steam leaks, maintaining steam traps, insulating hot surfaces, optimising blowdown using water-chemistry guidance, returning suitable condensate, reducing unnecessary steam demand and evaluating an economiser where technically and economically justified. Insulation and steam-distribution improvements can reduce system losses even when the boiler itself is operating properly.

Each measure should be assessed using measured baseline data, expected savings, installation cost, safety and maintenance requirements. Savings should not be claimed without a documented calculation or post-implementation measurement.

12. SITE DATA REQUIRED FOR A CASE STUDY

To convert this literature review into a study of the actual boiler, collect the following from authorised records: manufacturer and model; serial number; rated steam capacity and units; design and operating pressure; fuel type; burner rating; fuel consumption; steam flow; steam pressure and temperature; feedwater temperature; feedwater and boiler-water test results; blowdown rate; flue-gas temperature and composition; operating hours; load profile; maintenance history; and calibration details for instruments. Do not publish confidential serial numbers or sensitive plant information without permission.

Recommended table for fieldwork: Parameter | Value | Unit | Source/Instrument | Date/Operating Load. Enter "not available" where data cannot be verified. If a performance test is conducted, state the test method, assumptions, uncertainty and measurement period.

Parameter	Value	Unit / source
Rated steam capacity	Not supplied	Nameplate / manual
Operating pressure	Not supplied	Gauge / log sheet
Parameter	**Value**	**Unit / source**
Fuel consumption	Not supplied	Meter / records
Steam flow	Not supplied	Flow meter / records
Feedwater temperature	Not supplied	Thermometer / records
Flue-gas readings	Not supplied	Combustion analyser

(This work is licensed under a Creative Commons Attribution 4.0 International License.)

International Journal of Engineering Research & Technology (IJERT)
ISSN: 2278-0181
Vol. 15 Issue 10 , October - 2026

13. DISCUSSION

The literature indicates that boiler performance depends on the complete steam system rather than a single component. Combustion control affects fuel use and flue-gas losses; water chemistry affects heat transfer and reliability; blowdown and condensate return influence water and energy consumption; and preventive maintenance supports safe operation. A packaged design can simplify installation, but it does not remove the need for competent attendance, inspections, correct water treatment or measurement-based optimisation.

For the specific unit discussed in this assignment, the available information is insufficient to confirm rated capacity, operating pressure, fuel consumption or efficiency. These are not minor omissions: they determine the validity of performance calculations and any conclusions about cost or energy savings.

14. CONCLUSION

This report has summarised the construction, working principle, components, performance calculations, water treatment, safety, maintenance and energy-conservation practices relevant to an industrial packaged steam boiler. Published BEE and DOE/FEMP resources provide a foundation for understanding boiler and steam-system efficiency. The next step for a unit-specific study is to verify the installed boiler's nameplate and manual, then collect reliable operating and water-quality data under approved procedures. Until such evidence is available, no measured efficiency or savings should be claimed.

REFERENCES

[1] Bureau of Energy Efficiency (BEE), *Energy Performance Assessment of Boilers*, Chapter 1. https://beeindia.gov.in/sites/default/files/4Ch1.pdf
[2] Bureau of Energy Efficiency (BEE), *Boilers*, Chapter 2. https://beeindia.gov.in/sites/default/files/2Ch2.pdf
[3] U.S. Department of Energy, *Improving Steam System Performance: A Sourcebook for Industry*, 2nd ed., 2012. https://www.nrel.gov/docs/fy13osti/51710.pdf
[4] U.S. Department of Energy, Federal Energy Management Program, *Best Management Practice #8: Steam Boiler Systems*. https://www.energy.gov/cmei/femp/best-management-practice-8-steam-boiler-systems
[5] U.S. Department of Energy, *Steam Systems*. https://www.energy.gov/cmei/ito/steam-systems
[6] Access note: web addresses are provided for source verification. Consult the latest applicable editions and local regulations when preparing an operational or statutory document.

Appendix A: Suggested Observation Sheet

Record date/time, boiler load, steam pressure, steam temperature (if applicable), feedwater temperature, fuel consumption, feedwater flow, steam flow, flue-gas temperature, oxygen/CO■ reading, blowdown status, water-treatment results, alarms, and operator remarks. Record instrument identification and units. Take readings only when authorised and without interfering with safe operation.

Appendix B: Limitations

This document is a literature-based academic draft, not a certified inspection report or operating instruction. The exact Combipack model and site conditions were not independently verified. No original test data, drawings, nameplate photograph or manufacturer manual was provided. Therefore, all unit-specific values and measured performance results remain to be supplied by the student from authorised records.

(This work is licensed under a Creative Commons Attribution 4.0 International License.)